| BattenLok HS / SuperLok Perimeter Trim Reference - Standard Trim Poge WBL0000 | | | | | |
|---|---|---|---|---|---|
| | | | | | |
| | | GUTTER LAP | GUTTER CAP | EXPANSION COVER | GUTTER CLIP |
| F730 | | 2" LAP | F731R/L | F644/F652 | F246 |
| | Roof Stitch Screw 12" O.C. Roof Color | 42" Tube Sealant (12) Fastener #14 Trim Color | 19" Tube Sealant (10) Fastener #14 Trim Color | (11) Fastener #14 Trim Color | (1) Roof Stitch Screw Roof Color(1) Roof Stitch Screw Trim Color |
| all Panel | | | | | |
| $1\frac{1}{4}$ " and $1\frac{1}{2}$ " Wall Panel | RAKE | RAKE LAP | RAKE CAP (On Mod) | RAKE CAP (Off Mod) | GABLE CLOSURE |
| | F756 | 2"LAP | F757/F2350 | F757/F2351 | F758 |
| | Roof Member Screw 24" O.C. Trim Color | 17" Tube Sealant (7) Fastener #14 (2) Roof Stitch Screw Trim Color | 24" Tube Sealant (9) Fastener #14 Trim Color | 17" Tube Sealant (9) Fastener #14 Trim Color (2) Fastener #1 24" Tape HW504 | (3) Wall Stitch Screw Trim Color |
| 1½" Wall Panel | <u></u> | | Mitered High High Side | High Side Rake | |
| d 1½" W | HIGHSIDE | HIGHSIDE LAP | OUTSIDE CORNER | INSIDE CORNER | |
| | F544 | 2" LAP | Right as Shown | Field Work | |
| 1 <mark>4</mark> " and | Roof Stitch Screw 4" O.C. Wall Stitch Screw 12" O.C. Trim Color | 22" Tube Sealant (9) Fastener #14 (3) Roof Stitch Screw Trim Color | 22" Tube Sealant (9) Fastener #14 (3) Roof Stitch Screw Trim Color | 22" Tube Sealant (9) Fastener #14 (3) Roof Stitch Screw Trim Color | |
| Bird Stop F82 x 1'-6" OUTSIDE CORNER Pight go shown | | Rake Gutter INSIDE CORNER | OUTSIDE CORNER | Gutter Gutter INSIDE CORNER | |
| Right as shown 17" Tube Sealant (19) Fastener #14 (2) Roof Stitch Screw Trim Color | | Field Work 26" Tube Sealant (12) Fastener #14 (2) Roof Stitch Screw Trim Color | Field Work 26" Tube Sealant (13) Fastener #14 Trim Color | Field Work 26" Tube Sealant (13) Fastener #14 Trim Color | |